

# Relatório de Alinhamento Vertical

RUA NOVA - SENHOR DO BONFIM, PENEDO/AL

GREIDE DE TERRAPLENAGEM

Curva Nº	Ponto	Estaca	Cota	Declividade	Comprimento		Fmáx(m)	Constante K	
					L1	L2		K1	K2
	Inicial	0+0,000	9,1721713	7,4155160					
1	PCV	0+10,000	9,9137230						
	PIV	1+0,000	10,6552747						
	PTV	1+10,000	11,2219786	5,6670390	10	10	-,0437119	-11,4385262	-11,4385262
2	PCV	1+10,005	11,2222619						
	PIV	2+0,000	11,7886825						
	PTV	2+9,995	12,6253661	8,3710210	10	10	,0675658	7,3928008	7,3928008
3	PCV	2+10,005	12,6262032						
	PIV	3+0,000	13,4628869						
	PTV	3+9,995	14,1398293	6,7728100	10	10	-,0399353	-12,5077353	-12,5077353
4	PCV	3+10,005	14,1405066						
	PIV	4+0,000	14,8174491						
	PTV	4+9,995	15,6522828	8,3525130	10	10	,0394728	12,6542778	12,6542778
5	PCV	4+10,005	15,6531181						
	PIV	5+0,000	16,4879519						
	PTV	5+9,995	17,2115460	7,2395600	10	10	-,0278099	-17,9612255	-17,9612255
6	PCV	5+10,005	17,2122699						
	PIV	6+0,000	17,9358640						
	PTV	6+9,995	18,9333876	9,9802250	10	10	,0684824	7,2938504	7,2938504
7	PCV	6+10,005	18,9343856						
	PIV	7+0,000	19,9319091						
	PTV	7+9,995	21,1622081	12,3091400	10	10	,0581938	8,5833960	8,5833960
8	PCV	7+10,005	21,1634390						
	PIV	8+0,000	22,3937380						
	PTV	8+9,995	24,3005006	19,0771600	10	10	,1691159	2,9535966	2,9535966
9	PCV	8+10,005	24,3024083						
	PIV	9+0,000	26,2091708						
	PTV	9+9,995	28,0008415	17,9256600	10	10	-,0287731	-17,3599644	-17,3599644
10	PCV	9+15,000	28,8980213						
	PIV	10+0,000	29,7943048						
	PTV	10+5,000	30,3482015	11,0779350	5	5	-,0855966	-1,4603380	-1,4603380
	Final	10+7,010	30,5708473						